TUMKUR DIVISION.

Notification dated 10th April 1932.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 3 P.M. of 9th May 1932, for restoring Bukkapatna-Nagenhalli Minor Tank, Regd. No. 163, Koratagere Taluk.

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed before the end of June 1933.

2. The plans, detailed estimates and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed both in words and figures.

4. Each tender must be accompanied by a deposit of rupees four hundred in cash or currency note as earnest money, and be superscribed "Tender for restoring Bukkapatna-Nagenhalli Minor Tank, Regd. No. 163 of Koratagere Taluk" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be cancelled, and earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On receipt of one of the tenders, the earnest money on rejected tender will be returned.

9. Percentage rates above or below the estimate amount will not be accepted.

10. No claims for enhanced rates will be entertained on any account after acceptance of tender.

11. The contractor will be dealt with in terms of the bond for any short progress or delay. In matters of all disputes about rates and measurements, quality of work, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding on the contractor.

12. Rates should be quoted both in words and figures for each item of work and lumpsum provisions are subject to modification as per data worked out during execution. The individual item of work under lumpsum provisions the rates tendered for similar items of work will be paid and for other items the rates as per schedule of rates will be paid at the discretion of the Executive Engineer.

Abstract estimate of quantities for raising the waste weir of Bukkapatna Tank, Regd. No. 163 of Koratagere Taluk.

No	Items of work	Per	Quantity	Rate	
				In figures	In words
	FUND AT R. L. 57·00.				
1	Removing jungle grown on bund ...	Grade	25		
2	Cutting grips and trenches ...	Ryd.	3366		
3	Earthwork to bund with watering and tamping.	,,	11414		
4	Turfing slopes ...	S.yd.	11836		
5	Rough stone work new ...	C.yd.	543		
6	Chiselling, painting and refixing grade stones.	No.	17		
7	Providing new grade stones complete ...	,,	4		
8	Do Register No. Stone ...	,,	1		
	STOPPING PERCOLATION IN BUND IN GRADES 4, 5, 6 and 17.				
1	Removing and stacking rough stone revetment.	C.yd.	264		

No.	Items of work	Per	Quantity	Rate	
				In figures	In words
2	Earthwork cutting front slope of bund etc. ..	C.yd.	198		
3	Benching rock	S.ft.	396		
4	Burnt brick in surki mortar ...	C.ft.	445		
5	Rough plastering with surki mortar ...	S.qr.	12·38		
6	Gravel backing to revetment ..	C.yd.	198		
7	Resetting revetment old	,,	176		
8	New stone work	,,	88		
	WASTE WEIR LEFT R. L. 53·00 (35')				
1	Earthwork excavation	C.yd.	31		
2	Dismantling masonry	C.ft.	180		
3	Resetting old stone work with now jelly ...	C.yd.	6		
4	New stone work	,,	23		
5	Burnt brick in surki mortar ...	C.ft.	992		
6	Burnt stone slabs 6" roughly dressed ...	S.ft.	23		
7	Dressing refixing old slabs ...	,,	51		
8	Cutting joggles and fixing key stones etc....	No.	16		
9	Concrete in surki mortar	C.ft.	158		
10	Plastering with surki mortar ...	S.qr.	7·53		
11	Jelly wedgin to weir	,,	11·22		
	RIGHT WEIR.				
1	Earthwork excavation	C.yd.	21		
2	Resetting old stone work	,,	5		
3	New stone work	,,	4		
4	Burnt brick in surki mortar ...	C.ft.	648		
5	Burnt stone slabs (6") roughly dressed ...	S.ft.	61		
6	Concrete in surki mortar	C.ft.	108		
7	Cutting steps in rock, etc	S.ft.	22		
8	Blasting hard rock	C.yd.	5		
9	Plastering with surki mortar ...	S.qr.	4·80		
10	Jelly wedging	,,	5·94		

Dated 10th April 1932.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 3 P.M., on 7th May 1932, for Restoring Kenchanahalli Minor Tank in Gubbi Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed before the end of June 1933.

2. The plans detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. and 5. P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed both in words and in figures.

4. Each tender must be accompanied by a deposit of Rs. 400 in cash or currency note as earnest money, and be superscribed "Tender for Restoring Kenchanahalli Minor Tank in Gubbi Taluk." in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual bond, in default of which, his tender will be cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On receipt of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimate amount will not be accepted.

10. No claim for enhanced rates will be entertained on any account after acceptance of tender.

11. The contractor will be dealt with in terms of the bond for any short progress or delay. In matters of all disputes about rates and measurements, quality of work, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final, and legally binding on the contractor.

12. Rates should be quoted both in words and figures for each item of work and lump-sum provisions are subject to modifications as per data worked out during execution. The individual item of work under lumpsum provisions the rates tendered for similar items of works will be paid and for other items, the rates as per schedule of rates will be paid at the discretion of the Excutive Engineer.

Abstract estimate of quantities for Restoring Kenchanahalli katte Minor Tank, in Chitnahalli Hobli of Gubbi Taluk.

Sl. No.	Items of work	Per	Quantity	Rate	
				In figures	In words
	Bund R. L. 58·00				
1	Clearing jungle	Grade	16		
2	Cutting steps and grips in the old bund and breach.	L. S.			
3	Clearing silt and sand in the breach ...	C.yd.	587		
4	Earthwork to bund including watering and tamping, consolidating etc., complete.	,,	8,534		
5	Puddle wall in breach	,,	431		
6	Breach filling with selected earth including watering tamping, etc. complete.	,,	2,878		
7	Turfing the slopes	S.yd.	4,579		
8	Providing and fixing new grade stones with figures cut and painted, etc., complete.	No.	16		
9	Do index stones	,,	16		
10	Do B. M. stones ..	,,	2		
11	Do registered number and date stone.	,,	1		
12	Do gauge stone	,,	1		
13	Rough stone revetment new ..	C·yd.	1,382		
	Sluice				
1	Earthwork cutting bund and refilling with consolidation.	C.yd.	117		
2	Concrete in surki mortar	C-ft.	202		
3	Burnt brick in surki mortar ...	,,	490		
4	Burnt stone slabs 6″ dressed, etc. ...	S.ft.	285		
5	Plastering with surki mortar ...	S.qr.	8·35		
6	Cutting orifice in slabs	..	...		
7	Providing teakwood plug with rod ...	..	...		
	Waste weir at 53·00				
1	Earthwork excavation for foundation to body wall of weir	C.yd.	18		
2	Concrete in surki mortar	C.ft.	255		
3	Burnt brick in surki mortar ...	,,	718		
4	Plastering with surki mortar ...	S.qr.	8·20		
5	Burnt stone slabs 6″ dressed over body wall, returns and steps.	S.ft.	135		
6	Rough stone apron new	C.yd.	48		
7	Clearing draft and approaches (chargable to bund only) extra rate for lead is given.	,,	330		

A. TANDONI RAO,
Executive Engineer.